

with or retard the progress of the work of the building.

This Contractor shall arrange in advance of the construction of the building, etc., for all openings in floors, walls, ceilings, partitions, etc., and do all cutting, etc., necessary for the work together with all patching required to place same in harmony with the surrounding work.

The entire system of soil, waste, drain and vent piping shall be tested as will be directed. In addition, the water system shall be completely flushed at all connections so as to remove all foreign matter from the piping before final connections are made to the fixtures and other equipment.

All piping and fixtures shall be properly protected at all times and all the pipe openings must be closed to exclude dirt. Upon completion this Contractor shall turn on water to all fixtures and other equipment and leave everything in a clean and perfect condition and in complete running order.

The attention of the Contractor is specially called that before actually arranging and laying out runs of piping, etc., that he consult the various architectural drawings and details, with special reference to dimensions, as no allowance will be made for extras due to not properly locating piping, fixtures, etc., with regard to said architectural design and structural details.

GENERAL DESCRIPTION.

The plumbing fixtures with all piping shown or required in connection therewith shall be installed in the various locations noted on the drawings. Particular attention is called that while the plans show the locations of fixtures and miscellaneous equipment, there may be some slight shifting of said fixtures and equipment,