

The Contractor shall accordingly do such work without additional cost.

Certain fixtures are now on hand in the Court of Appeals Bldg. This Contractor shall disconnect these fixtures, cap or plug the outlets, place same in first class condition and re-connect them in the building in the location shown on the drawings.

The downspouts shall be furnished and installed complete by the Plumbing Contractor from the roof drains provided under the General Contract~~s~~. The Plumbing Contractor shall make all connections complete. The storm water drainage from downspouts and areas shall be collected into two lines, one on each side of the building, run as shown on the plans and discharge at grade into gutter of St. Johns Street. The cutting of curb to accommodate these two lines shall be done in an approved manner by this Contractor.

The 2" connection shown near air washer shall be provided with trap and brought above floor for the use of the air conditioning contractor; the exact location to be given later.

The sanitary drainage from the building shall be collected as shown and run to the manhole shown at the rear of the building and discharge into existing 15" sanitary sewer in St. Johns St., in manhole constructed by this Contractor.

Immediately upon the award of the General Contract and the Plumbing Contract, the Plumbing Contractor shall install the main sanitary lines and provide connections for and install two (2) Vogel or approved equal frost proof closets for the use of the various mechanics during the construction of the building. Upon completion of the building, the Plumbing Contractor shall remove the fixtures ~~xxxx~~ and any temporary connections and complete the work as required