544

(456-508)

544

Herring Run

63RD ST.

62ND ST.

MANOR PL.

OLIVER

Baltimore County
Baltimore City

Moores Run

CONC. BRIDGE

PHILADELPHIA AV. (RD.)

BALTIMORE STAMPING & ENAMELING CO.
MFRS OF GALVANIZED, ENAMELED & TIN WARE

"A" STAMPING
"B" ENAMELING & W. HO.
"C" PRESS R'M
"D" ANNEALING
"E" ENAMELING & W. HO.

GALVANIZING

MIXING

FIRE PROOF CONSTR'N BUILT 1910

NIGHT WATCHMAN WITH HYD'L CLOCK. POWER-STEAM & ELEC. I.E.P. HEAT-STEAM. FUEL-COAL. CHEM. ENGRS. ONE 1,000 GAL. WORTHINGTON UNDERWRITERS' STEAM FIRE PUMP, SIZE-10"×10"×12", WITH 4-2½" HOSE CONN'S.

10,000 GAL. WAT. ELEV'D 85' ABOVE GROUND, ON STEEL TOWER.

B. & O. STEEL BRIDGE

CONC. BRIDGE

R. R.

ASH DUMP

EASTERN AV.

CITY INCINERATOR PLANT No 2

FIREPROOF CONSTR'N EXCEPT EXPOSED STEEL POSTS & BEAMS; CONC. FLS. GYPSUM SLAB RF. PILASTD WALLS

DUMP PIT

CONC. PLTF'M

HERRING RUN PARK

Herring Run

SCALE 100 FT. TO ONE INCH

100 50 0 100 200

Copyright 1936 by the Sanborn Map Co.

544