

October 10, 1913.

Circular No.

NEW YORK, PITTSBURGH & CHICAGO RAILROAD.

Preliminary Unit Prices for use in Comparison of Bids.

Grubbing and clearing	\$60. per acre
Earth excavation	\$25 per cu. yd.
Loose and solid rock	70¢ " " "
Overhaul (500 ft. free)	1¢ per yd. per station
Rip rap and slope wall	\$2. per sq. ft. yd.
Retaining walls	\$3. " cu. ft. " yd.
Tunnels double track and lined	\$150. per lin. ft.
Masonry and concrete structures	\$8. per yd.
Superstructure, erected	3¢ per lb.
Viaducts not over 15' high	\$110. per lin. ft.
" between 15 and 150' high	\$150. " " "
" over 150' high	\$200. " " "
Foundations, bridge	\$5. " sq. ft.
Foundations, caissons (displacement)	\$25 per cu. ft.